

IMPORTANT!

Customers/plumbers should read this additional page before installation.

Sealing must be carried out prior to securing the panels together and securing the panels to the tray.

Seal between the underside of the frame/panel and the tray.

Seal between the frame/panels.

Do not seal on the inside.

Sealing should still be done on the outside as indicated later in this guide.

